

ATLANTIC TESTING LABORATORIES, LIMITED

atl

Box 29
Canton, N.Y. 13617
(315) 386-4578

Box 356
Cicero, N.Y. 13039
(315) 699-5281

August 31, 1989

U.S. Army Engineering Division, New England
424 Trapelo Road
Waltham, MA 02254-9149

Attn: Chief, Engineering Division

Re: Delivery Order No. 0010
Cape Cod Canal, Massachusetts
ATL Project No. CD036-89

Gentlemen:

The original report for the referenced project is enclosed for your review.

By copy of this letter, we are transmitting two copies of this report to the Chief, Geotechnical Engineering Branch, NEDED-G.

Sincerely,

Sharon M. Fullerton for/
Spencer F. Thew, P.E./L.S.

SFT/smf

Enc.

SECTION 1
Subsurface Investigation
Cape Cod Canal, Massachusetts

Contract No. DACW33-87-D-0007
Delivery order No. 0010

Contracting Officer:

Stanley J. Murphy, Lt. Colonel, CE
Deputy Division Engineer

PREPARED FOR: U. S. Army Corps of Engineers
New England Division
424 Trapelo Road
Waltham, MA 02254-9149

PREPARED BY: Atlantic Testing Laboratories, Limited
P.O. Box 29
Canton, New York 13617

ATL Report No. CD036-1-7-89

July 1989

SECTION 2

TABLE OF CONTENTS

| | |
|-----------|---|
| SECTION 1 | Title Page |
| SECTION 2 | Table of Contents |
| SECTION 3 | Scope of Investigation a. Delivery Order b. Project Site c. Purpose d. Scope of Work |
| SECTION 4 | Quality Control a. General Certification Statement b. Records Taken c. Equipment Used d. Procedures |
| SECTION 5 | Summary of Daily Activities and Telephone Log Table I Daily Activities Table II Telephone Log |
| SECTION 6 | Chain of Custody Log |
| SECTION 7 | Safety Reports |
| SECTION 8 | Field Inspector's Logs Boring Depths and Elevations Summary Cap Cod Canal Drawings Boring Location Plan Site Location |

SECTION 3

SCOPE OF INVESTIGATION

a. Delivery Order No. 00010

ORDER FOR SUPPLIES OR SERVICES

Form Approved
OMB No. 0704-0187
Expires Jul 31, 1989

PAGE 1 OF
2

| | | | | | | | | | |
|--|--|-------------------------------|--|--|--|---|--|--|--|
| 1. CONTRACT/PURCH ORDER NO. DADN338700007 | | 2. DELIVERY ORDER NO. 0010 | | 3. DATE OF ORDER. 06/19/89 | | 4. REQUISITION/PURCH REQUEST NO. 96131691660002 | | 5. CERTIFIED FOR NATIONAL DEFENSE UNDER DMS REG 1 DO | |
| 6. ISSUED BY Dept. of the Army 4. E. Division, Corps of Engrs 424 Trapelo Road Waltham, MA 02254-9149 Carol A. Devany (617)-647-8427 | | | | 7. ADMINISTERED BY See Block 6 | | 8. DELIVERY FOB (X) DEST [] OTHER (see schedule if other) | | 9. CONTRACTOR CODE 00001586 FACILITY CODE NAME AND ADDRESS ATLANTIC TESTING LAB, LIMITED P. O. BOX 29 CANTON, NY 13617- | |
| 10. DELIVER TO FOB POINT BY 07/27/89 | | | | 11. MARK IF BUS. IS (X) SMALL [] SMALL DISADVANTAGED [] WOMEN-OWNED | | 12. DISCOUNT TERMS 0 % 0 Net 0 | | | |
| 13. MAIL INVOICES TO SEE BLOCK 15 | | | | 14. SHIP TO CODE GEB Geotechnical Engineering Branch, Engineering Division, at issuing office. DADN338700007/0010 | | | | | |
| 15. PAYMENT WILL BE MADE BY Finance & Accounting Officer U.S.A. Engr. Div., New England 424 Trapelo Road Waltham, MA 02254-9149 | | | | 16. MARK ALL PACKAGES AND PAPERS WITH CONTRACT OR ORDER NUMBER | | | | | |

16. DELIVERY ☒ This delivery order is issued on another Government agency or in accordance with and subject to terms and conditions of above numbered contract.

PURCHASE ☐ Reference your furnish the following on terms specified herein.

ACCEPTANCE. THE CONTRACTOR HEREBY ACCEPTS THE OFFER REPRESENTED BY THE NUMBERED PURCHASE ORDER AS IT MAY PREVIOUSLY HAVE BEEN OR IS NOW MODIFIED, SUBJECT TO ALL OF THE TERMS AND CONDITIONS SET FORTH, AND AGREES TO PERFORM THE SAME.

NAME OF CONTRACTOR SIGNATURE TYPED NAME AND TITLE DATE SIGNED

☐ If this box is marked, supplier must sign Acceptance and return the following number of copies:

17. ACCOUNTING AND APPROPRIATION DATA/LOCAL USE
96x3123 CAB03344E000000 MD \$16,644.00

| 18. ITEM NO. | 19. SCHEDULE OF SUPPLIES/SERVICE | 20. QUANTITY ORDERED/ACCEPTED* (est) | 21. UNIT | 22. UNIT PRICE | 23. AMOUNT (est) |
|--------------|-----------------------------------|--------------------------------------|----------|----------------|------------------|
| 0001AC | Geologist | 40 | HR | 42.000000 | 1680.00 |
| 0001AC | Per Diem — Overnight Stay | 4 | DA | 50.000000 | 200.00 |
| 0001AD | Mileage from Waltham, MA & Return | 150 | MI | 0.350000 | 52.50 |

*If quantity accepted by the Government is same as quantity ordered, indicate by x. If different, enter actual quantity accepted below quantity ordered and encircle.

24. UNITED STATES OF AMERICA
BY: STANLEY J. MURPHY, LTC CE, DUE CONTRACTING/ORDERING OFFICER

25. TOTAL 16644.00

26. QUANTITY IN COLUMN 20 HAS BEEN
[] INSPECTED [] RECEIVED [] ACCEPTED AND CONFORMS TO THE CONTRACT EXCEPT AS NOTED

27. SHIP. NO.
[] PARTIAL
[] FINAL

28. D.O. VOUCHER NO.

29. DIFFERENCES

30. INITIALS

31. PAYMENT
[] COMPLETE
[] PARTIAL
[] FINAL

32. PAID BY

33. AMT VERIFIED CORRECT FOR

34. CHECK NUMBER

35. BILL OF LADING NO.

36. I certify this account is correct and proper for payment

DATE SIGNATURE OF AUTHORIZED GOVERNMENT REP.

DATE SIGNATURE AND TITLE OF CERTIFYING OFFICER

37. REC'D AT 38. RECEIVED BY 39. DATE REC'D 40. TOTAL CONT. 41. S/R ACCOUNT NUMBER 42. S/R VOUCHER NO.

ATLANTIC TESTING LAB. LIMITED

| ITEM NO. | SCHEDULE OF SUPPLIES/SERVICES | QUANTITY (est) | UNIT | UNIT PRICE | AMOUNT (est) |
|--------------------|---|-------------------|------|-------------|-----------------|
| 0001AD (continued) | | | | | |
| 0002AA | Geotechnical Report | 1 | JB | 924.000000 | 924.00 |
| 0004AA | Sample Delivery | 1 | JB | 140.000000 | 140.00 |
| 0006AA | Mobilization and Demobilization | 1 | JB | 1100.000000 | 1100.00 |
| 0006AB | Mileage from/to Waltham, Mass. | 150 | MI | 1.150000 | 172.50 |
| 0006AE | Standby time/on site moves | 16 | HR | 80.000000 | 1280.00 |
| 0010AB | 16 ft. boat | 3 | DA | 75.000000 | 225.00 |
| 0010AC | Operator for 12 ft. or 16 ft. boat | 3 | DA | 280.000000 | 840.00 |
| 0010AD | Standby time | 8 | HR | 35.000000 | 280.00 |
| 0010AI | 1500 square foot barge | 2 | DA | 2000.000000 | 4000.00 |
| 0010AJ | Standby time for 1500 square foot barge | 24 | HR | 125.000000 | 3000.00 |
| 0014AA | 0-50 ft. depth | 50 | LF | 25.000000 | 1250.00 |
| 0018AA | BX, MX size | 75 | LF | 20.000000 | 1500.00 |

ATTACHMENT NO. 1

GEB REQUISITION NO. 89-19 DACW33-87-D-0007

EXPLORATION INSTRUCTIONS

PROJECT: Borings and sampling.

SITE: Cape Cod Canal, MA

PURPOSE: Perform four borings to obtain bottom samples to a depth of -35 feet MLW at the East Mooring Basin in the Cape Cod Canal. This information is required to determine the character of sediment.

1. SCOPE OF INVESTIGATIONS

a. General. The East Mooring Basin is located in the Cape Cod Canal as shown on Attachment 2. Each boring will require continuous overburden sampling to a depth of -35 feet MLW. The entire samples will be saved.

b. Inspection.

(1) The services of one geotechnical field inspector are required during performance of the borings.

(2) All samples shall be delivered to the Corps of Engineers Headquarters in Waltham, MA by the field inspector. Sample delivery shall be coordinated with the Director, NED Materials and Water Quality Laboratory at (617)647-8367/8392.

c. Surveys. Boring locations are shown on the detailed plan provided separately. The Contractor shall tape off distances from the dolphins and otherwise position the barge visually from local fixed landmarks. A tideboard shall be placed on a dolphin for the Contractor's use by the Government.

2. SITE CONDITIONS

The Mooring Basin is located in the Cape Cod Canal as shown on Attachment 2. Exact locations of the four borings are shown on a detailed plan provided separately. Each boring will extend to a depth of -35 feet MLW. Water depths range from about -18.6 to -24.8 feet MLW at the boring locations. The tide range is about 8.7 feet. Bottom materials are likely to be silty to gravelly sands. There is access to the drilling site by water. Currents in the Canal can be swift. Sufficient power to maneuver the work barge shall be available whenever moving is necessary.

3. COORDINATION

The Contractor shall notify both Mr. Yuri Yatsevitch (617 647-8387) and Mr. Frank Ciccone (508 759-4413), Corps of Engineers, of the exact start date of drilling at least 5 days in advance. During the work, the inspector shall provide daily telephone reports to Mr. Yatsevitch.

The Contractor shall abide by all regulations governing operations in the Cape Cod Canal. Refer to navigation regulations stated in U.S. Dept. of Commerce publication "United States Coast Pilot, Atlantic Coast: Cape Cod to Sandy Hook" (furnished separately). Additional information can be

obtained by contacting the Canal office at 508 759-4413. While working in the Cape Cod Canal, the Contractor shall monitor channel 16 continuously and be capable of switching to channels 12 and 14 for communications with the Cape Cod Canal Office.

4. EXPLORATIONS

The drive sample borings designated FD-1 through 4 on the detailed location plan provided separately. The borings shall be numbered FD-89-1 through 4 in order of their completion on exploration logs and on a plan of explorations.

5. GOVERNMENT REVIEW

The Government will review the draft geotechnical report submittal as well as the completed report. Subsequent to such review, the Contractor shall accomplish any corrections which may be directed as a result of the Government review.

6. COMPLETION SCHEDULE

Services under this contract shall start within fourteen calendar days after receipt of the delivery order. Duration of the drilling is expected to be three calendar days. The geotechnical report shall be submitted in draft format for review by the Government no later than fourteen calendar days after completion of the drilling portion of the field work. The final geotechnical report shall be submitted no later than seven calendar days after receipt of the draft report including the action taken on possible comments.

8. QUALITY CONTROL

You will be held responsible for the quality of maps submitted and for all damages caused the Government as a result of your negligence in the performance of any services furnished under the contract.

Although submissions required by your contract are technically reviewed by the Government, it is emphasized that your work must be prosecuted using proper internal controls and review procedures. The letter of transmittal for each submission which you make shall include a certification that the submission has been subjected to your own review and coordination procedures to insure (a) completeness for each discipline commensurate with the level of effort required for that submission, (b) elimination of conflicts, errors, omissions, and (c) the overall professional and technical accuracy of the submission. Documents which are significantly deficient in any of these areas will be returned to you for correction and/or upgrading prior to our completing our review. Contract submission dates will not be extended if a resubmission of draft material is required for this reason.

CAPE COD BAY

CAPE COD CANAL LIGHTS

Mercury vapor lights, yellow on the north bank and white on the south bank are located 140 feet from the edge of the channel. The lights in general are 500 feet apart on both banks

PROJECT LOCATION

FIXED BRIDGE
HOR. CL. 500 FT.
VERT. CL. 125 FT.

Canal Breakwater
FIR 5s 43ft 14M 4"
HORN

TRAFFIC LIGHT
(see note)


Town Neck Hill

Sandwich

AIDS TO NAVIGATION

Consult U.S. Coast Guard Light List for supplemental information concerning aids to navigation.

ATTACHMENT 2



b. Project Site

The investigation took place in the mooring basin of the Cape Cod Canal in Massachusetts.

A General Plan, Boring Location Plan and two cross sections are included in Section 8. The plans were provided to us in the Delivery Order.

c. Purpose

The purpose of the exploration was to provide information regarding the character of the sediment material at the East Mooring Basin in the Cape Code Canal.

d. Scope of Work

Inspection and exploration instructions, which were provided by the Army Corps of Engineers, New England Division, in Delivery Order No. 0010, are included in Section 3a. General inspection and exploration instructions were provided by the Army Corps of Engineers, New England Division, through the contracted Geotechnical Exploratory Work Various Locations in New England. All correspondence with USACE representatives of inspection and exploration can be found listed in Table I, Daily Activities and Table II, Telephone Log, both included in Section 5.


Drilling and sampling was performed by Atlantic Testing Laboratories' personnel using Atlantic Testing Laboratories' equipment. The test borings were advanced and sampled as indicated on Attachment No. 1 of the Delivery Order (Section 3a) and as outlined in the contract specifications.

SECTION 4
QUALITY CONTROL

a. General Certification Statement

I hereby certify that the records, equipment and procedures mentioned below were used to perform the subsurface exploration described herein. I also certify that the work was performed in a professional manner and meets the requirements set forth in the Delivery Order. This report has been subject to my review and is both complete and technically accurate.

CERTIFIED July 12, 1989


Spencer F. Thew, P.E./L.S.

b. Records Taken

Pertinent drilling procedures, sampling operations, and soil classifications were noted on the following forms provided for use by the Corps of Engineers:

- NED-121 Field Log of Test Boring, Summary
- NED-58 & 58A Field Log of Test Boring
- NED-59 Subsurface Water Observations and Boring
Location Sketch

Information outlining overburden characteristics were noted on the Field Log of Test Boring (NED 58 and 58A). A completed series of Field Logs, Surface Water Observations, Boring Location Sketches, and Boring Details are included in Section 8.

Sample jars were labeled using a waterproof black marker and were delivered to the USACE NED Materials and Water Quality Laboratory in Waltham, Massachusetts, on June 29, 1989. The samples were accepted by Richard Berger, USACE on June 29, 1989.

A summary of Daily Activities and Telephone Logs are Tables I and II of Section 5. A chain of custody log is included in Section 6. The Safety Meeting Report (NED 251) is included in Section 7.

c. Equipment Used

A listing of all pertinent equipment and supplies provided by Atlantic Testing Laboratories, Limited.

Drilling equipment:

- CME 45 skid mounted drill rig
- NX (3") casing with drive and spin shoes
- NX drill rod - 2 ft, 5 ft and 10 ft lengths used for sampling
- split spoon samplers, 2" O.D. x 2' in length with 140 lb hammer

Subcontracted equipment:

- 1500 sq ft barge
- crane
- tug boat
- power skiff
- boat slip
- 3 (500 lb) anchors
- 1 barge operator
- 2 tug boat operators (1 operator, 1 helper)
- 1 power skiff operator

d. Procedures

Four (4) borings were performed in the East Mooring Basin in the Cape Cod Canal. This involved locating boring sites, placing a CME 45 drill rig and equipment on a metal barge, towing the barge and equipment to the site, securing the barge, drilling and sampling through the water and into the overburden and demobilizing the barge and equipment.

1. Survey Procedures

Locations were determined by Vicky Murphy, ATL Geotechnical Inspector by the use of a tape and scaled distances from a boring location map provided by the USACE. Borings FD-1 (FD-89-1) through FD-4 (FD-89-4) were referenced using the dolphins and local fixed landmarks. Vertical control was referenced using a tideboard located on a bulkhead on the opposite shore, this elevation was checked by radio with the USACE.

2. Access Procedures

Access to the borings required a metal barge. The CME 45 drill rig was placed onto the barge with a crane at the docks in Woods Hole. A tug boat towed the barge to the site and to each boring location. The barge was secured with heavy ropes and 500 lb anchors.

While in the canal, the barge was accessed with the tug boat or power skiff.

3. Sampling and Drilling Procedures

Sampling techniques as described in the contract and in the delivery order, involved retrieving material using a 2' x 2" O.D. standard split spoon sampler with a 140 lb hammer dropped 30". Bore holes were cased with NX (3") casing with spin shoes in 2 ft, 5 ft and 10 ft lengths. The sampling interval was 2 ft.

Samples were classified in the field in accordance with ASTM D-2488. Soil samples were placed in sample jars. Sample boxes were labeled and delivered to the USACE NED Materials and Water Quality Laboratory on June 29, 1989. A chain of custody log was maintained to document custody of the samples between Atlantic Testing Laboratories and the Corps of Engineers.

The CME 45 skid rig was equipped to effectively advance each hole. The technique used is generally described as follows:

- Standard split spoon sampler with the drill steel was lowered through the water and then driven with 140 lb hammer 2 ft into soils.

- NX (3") casing was lowered over the sample rod to top of soils and then spun with water to the sample depth.
- Sample was extruded and operation was repeated.

Specific drilling procedures for each bore hole have been recorded on the boring logs contained in Section 8d.

SECTION 5
SUMMARY OF DAILY ACTIVITIES
AND
TELEPHONE LOG

TABLE I
DAILY ACTIVITIES LOG

CD036 - CAPE COD CANAL

- June 23, 1989
Friday
- ATL drillers mobilized the CME 45 skid rig to Clark Contractors yard in Woods Hole, MA.
- June 26, 1989
Monday
- Vicky Murphy, ATL Geotechnical Inspector, Randy Todd and Kevin Hawkins, ATL drillers met at 6 a.m. at ATL's Canton office to be briefed by Spencer Thew, President ATL, on the Cape Cod Canal project.
 - At 6:30 a.m., Vicky Murphy, Randy Todd and Kevin Hawkins flew out of Potsdam Airport.
 - 9:30 a.m. landed in Hyannis Airport, drove to Woods Hole, MA.
 - At 10 a.m. met with Dan Clark, Clark Contractors, and discussed the specifics of the project. Clark's 2-man crew and ATL's drill crew started loading the barge.
 - At 10:30 a.m. V. Murphy called the ACOE in Bourne, MA and informed Mr. Frank Morris, Assistant Engineer, of the time the barge would be arriving at the mooring basin. At this time, it was thought that the barge would arrive at the site at approximately 6:30 p.m. on June 26. Mr. Morris gave V. Murphy directions to the ACOE office by land and said he would relate the details of the job to V. Murphy when she arrived.
 - At 11 a.m., V. Murphy and R. Todd called Spencer Thew, ATL, to discuss extra equipment required for safe anchorage. Mr. Thew told V. Murphy to do whatever was necessary to make the job safe.
 - 10 a.m. to 5 p.m. loaded the drill rig and equipment onto the barge with crane, mobilized tug boat to Woods Hole, MA, secured tug boat and barge.
 - At 1:30 p.m., ATL personnel went to the ACOE office in Bourne, MA and met with Frank Morris, Assistant Engineer for the ACOE. Mr. Morris related to ATL personnel the details of the job.
 - Peter, ACOE, drove ATL personnel to the shoreline of the job site and to the marina where the barge would have to be docked at night.
 - Randy Todd and Kevin Hawkins, ATL drill crew, received permission from the ACOE to park the drill trailer in the parking lot at the ACOE office in Bourne, MA.
 - At 5 p.m. V. Murphy called Dan Clark to get the arrival time of the barge at the site. Mr. Clark informed V. Murphy that due to unfavorable tides and winds, the barge had not yet departed and would not be able to leave Woods Hole until approximately 6 a.m. on June 27. Dan estimated that the barge would be on site at 11:30 a.m. on June 27.
 - 5:30 p.m. terminated for the day.
 - 7-1/2 hours stand by time for drill crew (10 a.m. - 5:30 p.m.).

June 27, 1989
Tuesday

- 7 a.m. Vicky Murphy, ATL Geotechnical Inspector, Randy Todd and Kevin Hawkins, ATL drill crew on site.
- 7 a.m. to 11:30 a.m., stand by time. Barge and drill rig being mobilized to the site (4-1/2 hrs).
- At 8:15 a.m., Dan Clark called V. Murphy and confirmed the barge's arrival time to be 11:30 a.m.
- At 9:15 a.m., V. Murphy called Frank Ciccone, ACOE, Bourne, MA and informed him that the barge would be arriving on the site at approximately 11:30 a.m.
- At 9:30 a.m., V. Murphy called Mr. Yuri Yatsevitch and told him of the progress of the project. Mr. Yatsevitch told V. Murphy that he would try and make a site visit/inspection on June 28.
- At 10:15 a.m., ATL personnel went to the ACOE office in Bourne, MA to see if they could get a key to the gates for the access roads. Mr. Frank Morris, ACOE, told ATL personnel they would not be able to access the barge from the shore by the dolphins. The tug boat would have to pick them up at the marina opposite the dolphins.
- At 10:45 a.m., V. Murphy called Dan Clark to get the location where ATL personnel would be picked up. Chip of Clark Contractors told V. Murphy that Dan Clark and Steve, both of Clark Contractors, were on their way to the marina and would coordinate the pick up.
- At 11 a.m. Mr. Clark and Steve arrived at the marina and informed ATL personnel that the barge should be in sight soon. The tug boat was going to first secure the barge to the western dolphin and then come into the marina to get ATL personnel and Steve of Clark Contractors. Tim, Clark Contractors, was already on the barge.
- At 11:30 a.m., tugboat with one operator and one helper picked up ATL personnel and Steve, Clark Contractors.
- 11:30 a.m. to 1:30 p.m., positioning barge on FD-1, setting anchors, securing barge, assembling casing and cased through water.
- 1:30 - 2:30 p.m., performed sampling.
- 2:30 - 4 p.m., pulling casing and positioning barge on FD-2, setting anchors, securing barge, cased through water.
- 4 - 4:45 p.m., sampling.
- 4:45 - 6 p.m., pulling and disassembling casing; tug boat pulled the barge into the marina for the night; secured the barge as tides were changing.
- Power skiff and operator monitored and controlled water traffic during sampling program.
- 6 p.m. work terminated for the day.
- 6 - 6:30 p.m. safety meeting.
- 9-1/4 hours stand by/on-site moves.
 - 7 a.m. - 1:30 p.m. = 6-1/2
 - 2:30 - 4 p.m. = 1-1/2
 - 4:45 - 6 p.m. = 1-1/4

June 28, 1989
Wednesday

- 6:30 a.m., Vicky Murphy, ATL Geotechnical Inspector, Randy Todd and Kevin Hawkins, ATL drill crew, Clark Contractors' personnel and tug boat crew boarded the barge and tug boat.
- 6:30 - 8:30 a.m., positioning the barge on FD-3, setting anchors, securing barge, assembling casing and cased through water.
- 8:30 - 9:15 a.m., sampling.
- 9:15 - 10:15 a.m., pulling casing, positioning barge on FD-4, setting anchors, securing barge, cased through water.
- 10:15 - 11:30 a.m., sampling.
- 11:30 - 11:45 a.m., pulling casing, disassembling casing.
- At 11:30 a.m., Mr. Yuri Yatsevitch, ACOE, made a site visit and was on the shore by the dolphins.
- 11:45 a.m. - 1:30 p.m., pulled casing, pulled up anchors, tug boat pulled the barge into the marina.
- 1:30 - 3:30 p.m., secured and unloaded the barge, removed equipment and samples. Discussed when the barge would be towed back so that drill rig could be removed.
- At 1:30 p.m. V. Murphy called Frank Ciccone and informed him that the project was complete but the barge, with drill rig on it would have to remain at the marina until tides and winds were favorable in the canal - possibly June 29 in the afternoon or the morning of June 30.
- At 1:30 p.m., Mr. Yuri Yatsevitch arrived at the marina and spoke with V. Murphy. Mr. Yatsevitch wanted to know findings.
- Power skiff and operator monitored and controlled water traffic during sampling program.
- 3:30 p.m. work terminated for the day.
- 6-3/4 hours stand by time/on site moves.
 - 6:30 - 8:30 a.m. = 2
 - 9:15 - 10:15 a.m. = 1
 - 11:45 - 3:30 = 3-3/4

June 29, 1989
Thursday

- 6 a.m. - 3 p.m., ATL drill crew, tug boat crew, and barge operator demobilized barge and drill rig from marina to Woods Hole, MA; unloaded drill rig and equipment.
- 6 a.m. - 7 a.m., V. Murphy organized samples and logs for delivery to USACE.
- 9 hours stand by time for drill crew.
 - 6 a.m. - 3 p.m. = 9

TABLE II
TELEPHONE ACTIVITY LOG

CD036 - CAPE COD CANAL

| | |
|---------------------------|--|
| June 15, 1989 Thursday | Patrick Sullivan, ATL to Yuri Yatsevitch, USACE at 9:15 a.m. P. Sullivan informed Y. Yatsevitch that ATL was prepared to start work on Monday, June 26, 1989. Y. Yatsevitch told P. Sullivan that he would start the paper work, FAX ATL a copy and put the original in the mail. |
| June 22, 1989 Thursday | Patrick Sullivan, ATL to Yuri Yatsevitch, USACE at 10:15 a.m. P. Sullivan confirmed to Y. Yatsevitch that ATL would start work on Monday, June 26. Patrick Sullivan, ATL to Frank Ciccone, USACE at 11:45 a.m. P. Sullivan left a message with the secretary regarding ATL beginning work on Monday morning at the East Mooring Basin. |
| June 26, 1989 Monday | Vicky Murphy, ATL to Frank Morris, USACE, 10:30 a.m. V. Murphy informed F. Morris of the barge's arrival time on the site. F. Morris gave V. Murphy directions, by land, to the USACE office in Bourne, MA and said he would relate the job details to V. Murphy when she arrived. Vicky Murphy, ATL to Spencer Thew, ATL, 11 a.m. V. Murphy discussed the extra equipment required for safe anchorage. S. Thew told V. Murphy to do whatever necessary to make the job safe. Vicky Murphy, ATL to Daniel Clark, Clark Contractors, 5 p.m. V. Murphy called to find out the time the barge would arrive on site. D. Clark informed V. Murphy that due to unfavorable tides and winds, the barge had not yet departed and would not be able to leave Woods Hole until 6 a.m. on June 27. D. Clark estimated that the barge would be on site at 11:30 a.m. on June 27. |

June 27, 1989
Tuesday

Daniel Clark, Clark Contractors to Vicky Murphy, ATL
8:15 a.m.

D. Clark confirmed to V. Murphy that the barge would
be arriving on the site at approximately 11:30 a.m.

Vicky Murphy, ATL to Frank Ciccone, USACE, 9:15 a.m.

V. Murphy informed F. Ciccone that the barge would be
arriving on the site at approximately 11:30 a.m.

Vicky Murphy, ATL to Yuri Yatsevitch, USACE,
9:30 a.m.

V. Murphy informed Y. Yatsevitch of the progress of
the project.

Y. Yatsevitch told V. Murphy that he would try and
make a site visit/inspection on June 28.

Vicky Murphy, ATL to Chip, Clark Contractors,
10:45 a.m.

V. Murphy asked Chip the location where ATL personnel
would be picked up to access the barge. Chip in-
formed V. Murphy that ATL personnel would be met by
D. Clark and Steve of Clark Contractors at the marina
and D. Clark would coordinate the pick up.

June 28, 1989
Wednesday

Vicky Murphy, ATL to Frank Ciccone, USACE, 1:30 p.m.

V. Murphy informed F. Ciccone that the project was
complete but the barge, with drill rig on it, would
have to remain at the marina until tides and winds
were favorable in the canal (possible June 29 in the
afternoon or June 30 in the morning).

June 29, 1989
Thursday

Randy Todd, ATL to Richard Berger, USACE, 10:30 a.m.

R. Todd called to inform the USACE NED Materials and
Water Quality Laboratory in Waltham, MA that he would
be delivering the soil samples.

R. Berger gave R. Todd directions to the laboratory.

Yuri Yatsevitch, USACE to Vicky Murphy, ATL,
11:45 a.m.

Y. Yatsevitch left a message with ATL secretary
saying he needed a copy of the logs faxed to him on
this date with designations and elevations.

June 29, 1989 Continued -

Vicky Murphy, ATL to Yuri Yatsevitch, USACE, 3 p.m.

V. Murphy asked Y. Yatsevitch if he could wait for the logs until the following day, and if these would be unofficial.

Y. Yatsevitch told V. Murphy that he could wait until June 30 for the logs and that they would be unofficial.

SECTION 6
CHAIN OF CUSTODY LOG

(317) - 171 - 367, 10397



atl

ATLANTIC TESTING LABORATORIES, Limited

CHAIN OF CUSTODY LOG FOR SOIL SAMPLES & ROCK CORES

Boring Logs: _____

Jar Samples: 2 Boxes (23 samples) FD1, FD2, FD3, FD4

Rock Cores: _____

Tubes: _____

DATE & TIME
OF TRANSFER

FROM

TO

LOCATION

SIGNATURE OF RECEIVER

6/29/89

Cape Cod

Waltham

Richard L. Berger

SECTION 7
SAFETY REPORTS

WEEKLY SAFETY MEETING

NEDSO

Date held 6/27/89

THRU: Area Engineer, _____ Area

Time 6:00 P.M.

TO: Safety Office, NED

1. Weekly safety meeting was held this date for the following personnel:

Contract No. DACW 33 - 87-D-0007 Contractor _____

Conducted By Vicky L. Murphy Personnel present (Contr) ATL (3)
(Sub) DAVID CLARK CONTRACTORS (4)
(Govt) _____

Subjects discussed (Note, delete, or add):

Individual Protective Equipment - ✓
Prevention of Falls - ✓
Safe Lifting Techniques - ✓
Emergency Communications - ✓
Fire Prevention - ✓
Sanitation, First Aid - ✓
Tripping Hazards - trash, hose, nails in lumber - ✓
Staging, Ladders, Concrete Forms -
Hand Tools, Portable Power Tools, Woodworking Machinery -
Equipment Maintenance (Zero defects) - ✓
Hoisting Equipment - ✓
Ropes, Hooks, Chains and Slings - ✓
Electrical Grounding, Temporary Wiring -
Lockouts for safe clearance procedures - electrical, pressure, moving parts
Welding -
Excavations -
Loose Rock and Steep Slopes -
Explosives - ✓
Water Safety - ✓
Other -

Prepared by Vicky L. Murphy Title I.E.

2. Forwarded.

Signature _____

Resident Engineer

CF:

SECTION 8
FIELD INSPECTOR'S LOGS

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site CAPE COD CANAL PROJECT NO. CD 036
 Hole No. FD-89-1 Diam. (Casing) 3 in. (NX) Page 1 of 4 Pages
 Co-ordinates: SEE BORING LOCATION PLAN Boring Started 6/27/89 1:00 pm
 Drilled by Atlantic Testing Laboratories, Limited Boring Completed 6/27/89 2:45 pm
Randy Todd and Kevin Hawkins Report Submitted _____
 Purpose of Exploration To determine the character of sediment

Elevation Top of Hole -24 ft. below M.L.W.
 Total Overburden Drilled 12 Feet
 Elevation Top of Water +0.5 ft. above M.L.W.
 Elevation Bottom of Hole -36 ft. below M.L.W.
 Total Rock Drilled 0.0 Feet
 Total Depth of Hole 36.5 Feet
 Core Recovered _____ %
 Core Recovered _____ Ft.; _____ Diam. _____ In.
 Soil Samples 13/8 In. Diam. 6 No.
 Soil Samples _____ In. Diam. _____ No.

Casing Left in Place 0.0 Feet
 Total length of casing 40.5 Feet
6' of casing through barge
(see boring detail page 4)

Water Table Depth +0.5 ft. above M.L.W.
24.5 ft. of water above top of soils

| Depth | | Method of Drilling and Type of Bit Used |
|-------|-------|--|
| From | To | |
| 0.0 | 10.0' | NX Casing, using water (3") |
| 0.0 | 12.0' | 1 3/8" I.D. Standard Split Spoon Sampler with 140 lbs. Hammer |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| INDEX | |
|------------------------|-----------------------|
| Ground Water | Back of Page <u>1</u> |
| Boring Location Sketch | Back of Page <u>1</u> |
| Overburden Record | Page <u> </u> |
| Rock Drilling | Page <u> </u> |
| Boring Detail | Page <u>4</u> |
| | Page <u> </u> |
| | Page <u> </u> |


Prepared by Vicky L. Murphy
 Submitted by Atlantic Testing Laboratories, Ltd.

Lab. Data

GROUND WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below



U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site CAP COD CANAL Page 2 of 4 Pages

Boring No. FD-89-1 Desig. _____ Diam. (Casing) 3"

FIELD LOG OF TEST BORING

Co-ordinates: SEE BORING LOCATION PLAN

Elevation Top of Boring -24 ft. below M.L.W. Hammer Wt. 140 lbs. Boring Started 6/27
Total Overburden Drilled 12 Feet Hammer Drop 30 in.
Elevation Top of Water +0.5 ft above M.L.W. Casing Left 0-0 Boring Completed 6/27
Total Rock Drilled 0-0 Feet Surface Water Data Back of Page 1
Elevation Bottom of Boring -36 ft. below M.L.W. Obs. Well _____
Total Depth of Boring 36.5 Feet Drilled By Randy Todd and Kevin Hawkins
Core Recovered _____ % No. Boxes _____ Mfg. Des. Drill CME 45
Core Recovered _____ Ft : _____ Diam. _____ In. Inspected By: Vicky L. Murphy
Soil Samples 13 In. Diam. 6 No. Classification By: Vicky L. Murphy
Soil Samples _____ In. Diam. _____ No. Classification By: _____

| DEPTH ft. | CORE/SAMPLE | | | BLOWS PER FT. CORE REC'Y | SAMPLING AND CORING OPERATIONS | CLASSIFICATION OF MATERIALS |
|--------------|-------------|--------|----------------|-----------------------------------|---|---|
| | NO. | SIZE | DEPTH RANGE | | | |
| | 1 | 1 3/8" | 2' | 1 | W.O.H. W.O.H. W.O.H. Sampled with 1 3/8" I.D. spoon with 140 lbs. hammer to -26 ft. below MLW. | Greyish-Brown f SAND; trace SILT (s, np) Recovery = 4" = 17% |
| | 2 | 1 3/8" | 4' | 4 | 5 Spun 3" casing 6 ft. through barge, 24.5 ft. through water and 2 ft. through soils to 26.5 ft. below existing water level (-26' below MLW) W.O.H. Sampled with 1 3/8" I.D. spoon to -28 ft. below M.L.W. | Grey mf SAND; little f GRAVEL; trace SILT (s, np) Recovery = 1" = 4% |
| | 3 | 1 3/8" | 6' | 5 | 2 3 4 Spun 3" casing 2 ft. through soils to 28.5 ft. below existing water level (-28' below M.L.W.) Sampled with 1 3/8" I.D. spoon to -30 ft. below M.L.W. | Grey emf SAND; trace SILT (s, np) Recovery = 12" = 50% |
| | 4 | 1 3/8" | 8' | 12 | 11 10 10 Spun 3" casing 2 ft. through soils to 30.5 ft. below existing water level (-30' below MLW) Sampled with 1 3/8" I.D. spoon to -32 ft below MLW | Grey f SAND; trace SILT (s, np) Recovery = 10" = 42% |
| | 5 | 1 3/8" | 10' | 17 | 3 4 7 Spun 3" casing 2 ft. through soils to 32.5 ft. below existing water level (-32' below MLW) Sampled with 1 3/8" I.D. spoon to -34 ft. below MLW | Grey f SAND; little SILT (s, np) Recovery = 24" = 100% |

GENERAL REMARKS: W.O.H. - Weight of Hammer

M.L.W. - Mean Low Water

24.5 ft. of water above top of hole at start (1:00 pm)

Water Level = +0.5 ft above M.L.W. at 1:00 pm

SUBJECT

FD-89-1

JOB NO.

CD 036

BY

VLM


DATE

7/7/89

SHEET

4 of 4

BORING DETAIL



*All depths referenced to M.L.W. = mean Low Water = 0.00 ft.

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site CAPE COD CANAL PROJECT NO. CD 036
 Hole No. FD-89-Z Diam. (Casing) 3 in. (NX) Page 1 of 3 Pages
 Co-ordinates: SEE BORING LOCATION PLAN Boring Started 6/27/89 3:45 pm
 Drilled by Atlantic Testing Laboratories, Limited Boring Completed 6/27/89 5:00 pm
Randy Todd and Kevin Hawkins Report Submitted _____
 Purpose of Exploration To determine the character of sediment

Elevation Top of Hole -26.4 ft. below M.L.W.
 Total Overburden Drilled 8 Feet
 Elevation Top of Water +4.6 ft. above M.L.W.
 Elevation Bottom of Hole -34.4 ft. below M.L.W.
 Total Rock Drilled 0.0 Feet
 Total Depth of Hole 39.0 Feet
 Core Recovered _____ %
 Core Recovered _____ Ft.; _____ Diam. _____ In.
 Soil Samples 13/8 In. Diam. 4 No.
 Soil Samples _____ In. Diam. _____ No.

Casing Left in Place 0.0 Feet
 Total Length of Casing 43 Feet
6 ft. of casing through barge
(see boring detail page 3)

Water Table Depth +4.6 ft. above M.L.W.
31 ft. of water above top of soils

| Depth | | Method of Drilling and Type of Bit Used |
|-------|------|--|
| From | To | |
| 0.0' | 6.0' | NX Casing, using water (3") |
| 0.0' | 8.0' | 1 3/8" I.D. Standard Split Spoon Sampler with 140 lbs. Hammer |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |


| INDEX | |
|------------------------|-----------------------|
| Ground Water | Back of Page <u>1</u> |
| Boring Location Sketch | Back of Page <u>1</u> |
| Overburden Record | Page _____ |
| Rock Drilling | Page _____ |
| Boring Detail | Page <u>3</u> |
| | Page _____ |
| | Page _____ |

Prepared by Vicky L. Murphy Field Data
 Submitted by Atlantic Testing Laboratories, Limited Lab. Data

GROUND WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below mean low water (MLW)



U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site CAPE COD CANAL, MA Page 1 of 3 Pages

Boring No. FD-89-2 Desig. Diam. (Casing) 3 in.

FIELD LOG OF TEST BORING

Co-ordinates: SEE BORING LOCATION PLAN


Elevation Top of Boring -26.4 ft. below M. Hammer Wt. 140 lbs. Boring Started 6/27
Total Overburden Drilled 8 Feet Hammer Drop 30 in.
Elevation Top of +4.6 ft. above M. Casing Left 0.0 ft. Boring Completed 6/27
Total Rock Drilled 0.0 Feet Surface Water Data Back of Page 1
Elevation Bottom of Boring -34.4 ft. below M. Obs. Well
Total Depth of Boring 39.0 Feet Drilled By Randy Todd and Kevin Hawkins
Core Recovered % No. Boxes Mfg. Des. Drill CME 45
Core Recovered Ft : Diam. In. Inspected By: Vicky L. Murphy
Soil Samples 13/8 In. Diam. 4 No. Classification By: Vicky L. Murphy
Soil Samples In. Diam. No. Classification By:

| DEPTH | CORE/SAMPLE | | | BLOWS PER FT. CORE REC'Y | SAMPLING AND CORING OPERATIONS | CLASSIFICATION OF MATERIALS |
|-------|-------------|--------|----------------|-----------------------------------|---|---|
| | NO. | SIZE | DEPTH RANGE | | | |
| | | | | 3 | Sampled with 1 3/8" I.D. spoon with 140 lbs. hammer to - 28.4 ft below MLW | Grey mft SAND; trace SILT (s, np) - Sample contained traces of o.i Recovery = 18" = 75% |
| | | | | 3 | | |
| | | | | 5 | | |
| | 1 | 1 3/8" | 2' | 6 | | |
| | | | | 4 | Spun 3" casing 6 ft. through barge, 31 ft. through water and 2 ft. through soils to - 33 ft. below existing water level (- 28.4' below MLW) | Grey f SAND; little SILT (s, np) Recovery = 10" = 42% |
| | | | | 3 | | |
| | | | | 2 | | |
| | 2 | 1 3/8" | 4' | 3 | Sampled with 1 3/8" I.D. spoon to - 30.4 ft below MLW | |
| | | | | 3 | Spun 3" casing 2 ft. through soils to 35 ft. below existing water level (- 30.4' below MLW) | Grey f SAND; little SILT (s, np) Recovery = 24" = 100% |
| | | | | 2 | | |
| | | | | 3 | | |
| | 3 | 1 3/8" | 6' | 4 | Sampled with 1 3/8" I.D. spoon to - 32.4 ft. below MLW | |
| | | | | 14 | Spun 3" casing 2 ft. through soils to 37 ft. below existing water level (- 32.4' below MLW) | Grey f SAND; little SILT (s, np) |
| | | | | 10 | | |
| | | | | 9 | | |
| | 4 | 1 3/8" | 8' | 7 | Sampled with 1 3/8" I.D. spoon to - 34.4 ft. below MLW | |

GENERAL REMARKS: M.L.W. - Mean Low Water
31 ft. of water above top of hole at start (3:45 pm)
Water Level = +4.6 ft. above M.L.W. at 3:45 pm

| | | | | | | | | | |
|---------|---------|---------|--------|----|-----|------|--------|-------|--------|
| SUBJECT | FD-89-2 | JOB NO. | CD 036 | BY | VLM | DATE | 7/6/89 | SHEET | 3 of 3 |
|---------|---------|---------|--------|----|-----|------|--------|-------|--------|

BORING DETAIL



* All depths referenced to M.L.W. = Mean Low Water = 0.00 ft.

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site CAPE COD CANAL PROJECT NO. CD-036
 Page 1 of 3 Pages
 Hole No. FD-89-3 Diam. (Casing) (NX) 3 in. Boring Started 6/28/89 8:15 am
 Co-ordinates: SEE BORING LOCATION PLAN Boring Completed 6/28/89 9:30 am
 Drilled by Atlantic Testing Laboratories, Limited
Randy Todd and Kevin Hawkins Report Submitted _____
 Purpose of Exploration To determine the character of sediment

Elevation Top of Hole +25.2' below M.L.W.
 Total Overburden Drilled 10 Feet
 Elevation Top of Water +7.8' above M.L.W.
 Elevation Bottom of Hole -35.2 below M.L.W.
 Total Rock Drilled 0.0 Feet
 Total Depth of Hole 43.0 Feet
 Core Recovered _____ %
 Core Recovered _____ Ft.; _____ Diam. _____ In.
 Soil Samples 1³/₈ In. Diam. 5 No.
 Soil Samples _____ In. Diam. _____ No.

Casing Left in Place 0.0 Feet

Total length of Casing 47.0 Feet
6 ft. of casing through barge
(see boring detail)

Water Table Depth +7.8' above M.L.W.
33 ft. above top of soils

| Depth | | Method of Drilling and Type of Bit Used |
|-------|------|---|
| From | To | |
| 0.0 | 8.0 | NX CASING using water (3") |
| 0.0 | 10.0 | 1 ³ / ₈ " I.D. Standard Split Spoon Sampler |
| | | with 140 lb. hammer |
| | | |
| | | |
| | | |
| | | |
| | | |

| INDEX | |
|------------------------|-----------------------|
| Ground Water | Back of Page <u>1</u> |
| Boring Location Sketch | Back of Page <u>1</u> |
| Overburden Record | Page _____ |
| Rock Drilling | Page _____ |
| Boring Detail | Page <u>3</u> |
| | Page _____ |
| | Page _____ |

Prepared by Vicky L. Murphy
 Submitted by Atlantic Testing Laboratories, Limited

GROUND WATER OBSERVATIONS


[illegible]

Note: Depths are in feet below M.L.W.

SCUSSET
BEACH

BORING LOCATION SKETCH

Scale: 1" = 200'



U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site CAPE COD CANAL Page 2 of 3 Pages

Boring No. FD-89-3 Desig. _____ Diam. (Casing) 3"

FIELD LOG OF TEST BORING

Co-ordinates: SEE BORING LOCATION PLAN

Elevation Top of Boring -25.2' below M.L.W. Hammer Wt. 140 lbs. Boring Started 6/28/89
Total Overburden Drilled 10 Feet Hammer Drop 30 in.
Elevation Top of Water +7.8' above M.L.W. Casing Left 0.0 ft. Boring Completed 6/28/89
Total Rock Drilled 0.0 Feet Surface Water Data Back of Page 1
Elevation Bottom of Boring -35.2' below M.L.W. Obs. Well _____
Total Depth of Boring 43.0 Feet Drilled By Randy Todd and Kevin Hawkins
Core Recovered _____ % No. Boxes _____ Mfg. Des. Drill CME 45
Core Recovered _____ Ft : _____ Diam. _____ In. Inspected By: Vicky L. Murphy
Soil Samples 1^{3/8} In. Diam. 5 No. Classification By: Vicky L. Murphy
Soil Samples _____ In. Diam. _____ No. Classification By: _____


| DEPTH | CORE/SAMPLE | | | BLOWS PER FT. CORE REC'Y | SAMPLING AND CORING OPERATIONS | CLASSIFICATION OF MATERIALS |
|-------|-------------|-------------------|----------------|-----------------------------------|---|---|
| | NO. | SIZE | DEPTH RANGE | | | |
| | | | | W.O.H. | Sampled with 1 ^{3/8"} I.D. spoon with 140 lbs. Hammer | Grey mf + SAND; trace SILT (s, np) - Sample contained traces of oil Recovery = 18" = 75% |
| | | | | W.O.H. | | |
| | 1 | 1 ^{3/8"} | 2' | 3 | | |
| | | | | 5 | | |
| | | | | 3 | SPUN 3" CASING 6 ft. through barge, 33 ft. through water and 2 ft. through soils (-27.2' below MLW) | Dark Grey mf + SAND; trace SILT (s, np) - Sample contained traces of oil. Recovery = 8" = 33% |
| | | | | 2 | | |
| | | | | 7 | Sampled with 1 ^{3/8"} I.D. spoon with 140 lbs. Hammer | |
| | 2 | 1 ^{3/8"} | 4' | 6 | | |
| | | | | 4 | Spun Casing 2 ft. through soils to 37 ft. below existing water level (-29.2' below MLW) | Grey SILT and f SAND; trace CLAY (s, vsp) Recovery = 10" = 42% |
| | | | | 4 | | |
| | | | | 3 | Sampled with 1 ^{3/8"} I.D. spoon with 140 lbs. Hammer | |
| | 3 | 1 ^{3/8"} | 6' | 4 | | |
| | | | | 3 | SPUN 3" CASING 2 ft. through soils to 39 ft. below existing water level (-31.2' MLW) | Grey SILT; some CLAY; little f SAND (s, p) Recovery = 20" = 83% |
| | | | | 3 | | |
| | | | | 4 | Sampled with 1 ^{3/8"} I.D. spoon with 140 lbs. hammer | |
| | 4 | 1 ^{3/8"} | 8' | 9 | | |
| | | | | | SPUN 3" CASING 2 ft. into soils to 41 ft. below existing water level (-33.2' below MLW) | Grey f SAND and SILT (s, np) Recovery = 18" = 75% |
| | | | | | | |
| | | | | | Sampled with 1 ^{3/8"} I.D. spoon with 140 lbs. hammer | |
| | 5 | 1 ^{3/8"} | 10' | | | |

GENERAL REMARKS: W.O.H. - Weight of Hammer
M.L.W. - Mean Low Water

- 33 ft. of water above top of hole at start (8:15 am)
- Water level = +7.8' above M.L.W. at 8:15 am (±)

| | | | | | | | | | |
|---------|---------|---------|--------|----|-----|------|--------|-------|--------|
| SUBJECT | FD-89-3 | JOB NO. | CO 036 | BY | VLM | DATE | 7/3/89 | SHEET | 3 OF 3 |
|---------|---------|---------|--------|----|-----|------|--------|-------|--------|

BORING DETAIL



* All depths referenced to M.L.W. = MEAN LOW WATER = 0.00

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site CAPE COD CANAL PROJECT NO. CD 036
 Hole No. FD-89-4 Diam. (Casing) (NX) 3 in. Page 1 of 4 Pages
 Co-ordinates: SEE BORING LOCATION PLAN Boring Started 6/28/89 10:00 am
 Drilled by Atlantic Testing Laboratories, Limited Boring Completed 6/28/89 11:45 am
Randy Todd and Kevin Hawkins Report Submitted _____
 Purpose of Exploration To determine the character of sediment

Elevation Top of Hole -18.9' below M.L.W. Casing Left in Place 0.0' Feet
 Total Overburden Drilled 16 Feet Total Length of Casing 44.5 Feet
 Elevation Top of Water +5.6' above M.L.W. 6 ft. of casing through barge
 Elevation Bottom of Hole -34.9' below M.L.W. (see boring detail page 4)
 Total Rock Drilled 0.0 Feet
 Total Depth of Hole 40.5 Feet
 Core Recovered _____ %
 Core Recovered _____ Ft.; _____ Diam. _____ In.
 Soil Samples 13/8 In. Diam. 8 No.
 Soil Samples _____ In. Diam. _____ No.
 Water Table Depth +5.6 ft. above MLW.
24.5 ft. above top of soils


| Depth | | Method of Drilling and Type of Bit Used | INDEX | |
|-------|-------|--|------------------------|-----------------------|
| From | To | | | |
| 0.0' | 14.0' | NX Casing, using water (3") | Ground Water | Back of Page <u>1</u> |
| 0.0' | 16.0' | 1 3/8" I.D. Standard Split Spoon Sampler | Boring Location Sketch | Back of Page <u>1</u> |
| | | with 140 lbs. Hammer | Overburden Record | Page _____ |
| | | | Rock Drilling | Page _____ |
| | | | Boring Detail | Page <u>4</u> |
| | | | | Page _____ |
| | | | | Page _____ |

Prepared by Vicky L. Murphy Field Data
 Submitted by Atlantic Testing Laboratories, Ltd. Lab. Data

GROUND WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below M.L.W. - Mean Low Water



U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site CAPE COO CANAL Page 2 of 4 Pages

Boring No. FD-89-4 Desig. _____ Diam. (Casing) 3 in.

FIELD LOG OF TEST BORING

Co-ordinates: SEE BORING LOCATION PLAN


Elevation Top of Boring -18.9' below M.L.W. Hammer Wt. 140 lbs. Boring Started 6/28/89
Total Overburden Drilled 16 Feet Hammer Drop 30 in.
Elevation Top of Water +5.6' above M.L.W. Casing Left 0-0 ft. Boring Completed 6/28/89
Total Rock Drilled 0-0 Feet Surface Water Data Back of Page 1
Elevation Bottom of Boring -34.9' below M.L.W. Obs. Well _____
Total Depth of Boring 40.5 Feet Drilled By Randy Todd and Kevin Hawkins
Core Recovered _____ % No. Boxes _____ Mfg. Des. Drill CME 45
Core Recovered _____ Ft : _____ Diam. _____ In. Inspected By: Vicky L. Murphy
Soil Samples 1 3/8 In. Diam. 8 No. Classification By: Vicky L. Murphy
Soil Samples _____ In. Diam. _____ No. Classification By: _____

| DEPTH | CORE/SAMPLE | | | BLOWS PER FT. CORE REC'Y | SAMPLING AND CORING OPERATIONS | CLASSIFICATION OF MATERIALS |
|-------|-------------|--------|----------------|-----------------------------------|--|--|
| | NO. | SIZE | DEPTH RANGE | | | |
| | | | | W.O.H. | Sampled with 1 3/8" I.D. spoon with 140 lbs. hammer | Dark Grey mft SAND; little SILT (s.np) Recovery = 10" = 42% |
| | | | | 2 | | |
| | | | | 2 | | |
| | 1 | 1 3/8" | 2' | 2 | | |
| | | | | 7 | Spun 3" casing 6 ft. through barge, 24.5 ft. through water and 2 ft. through soils to 26.5 ft. below existing water level (-20.9' below MLW) | Dark Grey mft SAND; little SILT (s.np) Recovery = 10" = 42% |
| | | | | 6 | | |
| | | | | 9 | Sampled with 1 3/8" I.D. spoon with 140 lbs. hammer | |
| | 2 | 1 3/8" | 4' | 7 | | |
| | | | | 4 | Spun 3" casing 2 ft. through soils to 28.5 ft. below existing water level (-22.9 ft. below MLW) | Grey mft SAND; little SILT (s.np) Recovery = 18" (75%) |
| | | | | 3 | | |
| | | | | 5 | Sampled with 1 3/8" I.D. spoon with 140 lbs. hammer | |
| | 3 | 1 3/8" | 6' | 5 | | |
| | | | | 9 | Spun 3" casing 2 ft. through soils to 30.5 ft. below existing water level (-24.9 ft. below MLW) | Grey mft SAND; little SILT; trace m GRAVEL (s.np) Recovery = 24" = 100% |
| | | | | 17 | | |
| | | | | 47 | Sampled with 1 3/8" I.D. spoon with 140 lbs. hammer. | |
| | 4 | 1 3/8" | 8' | 51 | | |
| | | | | | Spun 3" casing 2 ft. through soils to 32.5 ft. below existing water level (-26.9 ft. below MLW) | Grey f SAND; some SILT (s.np) Recovery = 24" |
| | | | | | Sampled with 1 3/8" I.D. spoon with 140 lbs. hammer. | |
| | 5 | 1 3/8" | 10' | 19 | | |

GENERAL REMARKS: W.O.H. - weight of Hammer
M.L.W. - Mean Low Water
24.5 ft. of water above top of hole at start (10:00 a.m.)
Water Level = +5.6' above M.L.W. at 10:00 a.m.


| | | | | | | | | | |
|---------|---------|---------|--------|----|-----|------|--------|-------|--------|
| SUBJECT | FD-89-4 | JOB NO. | CD 036 | BY | VLM | DATE | 7/6/89 | SHEET | 4 of 4 |
|---------|---------|---------|--------|----|-----|------|--------|-------|--------|

BORING DETAIL



* All depths referenced to M.L.W. = Mean Low Water = 0.00 ft.

SITE LOCATION MAP




PROJECT No.
CD 036

U.S.G.S. QUADRANT:
Sagamore

SCUSSET
BEACH

4 BORINGS
TO
35' MLW



NOTE: ALL DISTANCES ARE APPROXIMATE

SANDWICH

BORING LOCATION PLAN

SCALE
1" = 200'

PROJECT No.
CD036

DATE
6/30/89

CAPE COD CANAL, MA

ATLANTIC TESTING LABORATORIES, Limited
CANTON NY CINCINNATI NY
BURLINGTON VT UTICA NY
ENDICOTT NY
MANCHESTER NH